BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2024-25/OW/WORK_INDENT3935

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/07/2024-25, Date: 09-09-2024

Name Of Work: Maintenance of Existing Borewells in ward no. 05 Kogilu Surrounding area.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NATARAJ T	
				In Figures	In Words
1	70.00	The lifting of submergible pumpset from well.	Each	1482.00	Rupees One Thousand Four Hundred Eighty Two Only
2	35.00	The Transportation of pumping machineries	Each	1185.60	Rupees One Thousand One Hundred Eighty Five and Sixty Paise Only
3	5.00	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months) Above 7.5 HP to up to 8.0 HP	Each	3970.77	Rupees Three Thousand Nine Hundred Seventy and Seventy Seven Paise Only
4	5.00	For all types of submersible pumpsets above 10 HP and upto 11 H.P.	Each	5095.12	Rupees Five Thousand Ninety Five and Twelve Paise Only
5	10.00	For all types of submersible pumpsets above 12 HP and upto 13 H.P	Each	5911.20	Rupees Five Thousand Nine Hundred Eleven and Twenty Paise Only
6	15.00	For all types of submersible pumpsets 15HP to 20 HP	Each	8822.84	Rupees Eight Thousand Eight Hundred Twenty Two and Eighty Four Paise Only
7	25.00	Pump bowls of same type and make	No.	1482.00	Rupees One Thousand Four Hundred Eighty Two Only
8	25.00	Intermediate Piece (I.P) With IP Leaded Bronxe bush	No.	1037.40	Rupees One Thousand Thirty Seven and Forty Paise Only
9	35.00	Upper Flange	No.	642.20	Rupees Six Hundred Forty Two and Twenty Paise Only
10	35.00	lower Flange	No.	642.20	Rupees Six Hundred Forty Two and Twenty Paise Only
11	35.00	Upper/ Lower Housing	No.	1185.60	Rupees One Thousand One Hundred Eighty Five and Sixty Paise Only
12	35.00	Guide vane	No.	691.60	Rupees Six Hundred Ninety One and Sixty Paise Only
13	35.00	Impeller Shell moulded with aluminium Bronze	No.	1482.00	Rupees One Thousand Four Hundred Eighty Two Only
14	35.00	Discharge outlet (D.O) Bearing D.O Steel Bush	No.	2025.40	Rupees Two Thousand Twenty Five and Forty Paise Only
15	10.00	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages)	No.	1482.00	Rupees One Thousand Four Hundred Eighty Two Only
16	20.00	Pump Coupling (Stainless Steel)	No.	1482.00	Rupees One Thousand Four Hundred Eighty Two Only
17	40.00	Stud and Nuts	Each	197.60	Rupees One Hundred Ninety Seven and Sixty Paise Only

Signature of the Contractor

Executive Engineer

Name Of Work: Maintenance of Existing Borewells in ward no. 05 Kogilu Surrounding area.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NATARAJ T	
				In Figures	In Words
18	35.00	Motor Base With Pin	Each	494.00	Rupees Four Hundred Ninety Four Only
19	20.00	The Starter of Motor up to 4 to 5 HP	No.	3458.00	Rupees Three Thousand Four Hundred Fifty Eight Only
20	20.00	The Rotor of Motor up to 4 to 5 HP	No.	1976.00	Rupees One Thousand Nine Hundred Seventy Six Only
21	35.00	Carbon Housing	No.	1976.00	Rupees One Thousand Nine Hundred Seventy Six Only
22	35.00	The Carbon Housing (Thrust bearing block assembly complete with segment bearing pad).	No.	2173.60	Rupees Two Thousand One Hundred Seventy Three and Sixty Paise Only
23	30.00	Oil Seal	No.	345.80	Rupees Three Hundred Forty Five and Eighty Paise Only
24	30.00	Oil Seal Steel Bush	No.	247.00	Rupees Two Hundred Forty Seven Only
25	35.00	Steel bearing Bush	No.	395.20	Rupees Three Hundred Ninety Five and Twenty Paise Only
26	40.00	Allen Screw	No.	1185.60	Rupees One Thousand One Hundred Eighty Five and Sixty Paise Only
27	35.00	Pump Key (Stainless Steel)	No.	642.20	Rupees Six Hundred Forty Two and Twenty Paise Only
28	10.00	Non return valve (NRV) assembly complete with rubber 'O' Ring	No.	642.20	Rupees Six Hundred Forty Two and Twenty Paise Only
29	25.00	Cable Guard	No.	345.80	Rupees Three Hundred Forty Five and Eighty Paise Only
30	25.00	Strainer	No.	444.60	Rupees Four Hundred Forty Four and Sixty Paise Only
31	30.00	Brass Filter	No.	1037.40	Rupees One Thousand Thirty Seven and Forty Paise Only
32	30.00	Lock Ring	Each	345.80	Rupees Three Hundred Forty Five and Eighty Paise Only
33	30.00	The Carbon Housing (Top carbond / ferrodo padding)	Each	345.80	Rupees Three Hundred Forty Five and Eighty Paise Only
34	35.00	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush	Each	839.80	Rupees Eight Hundred Thirty Nine and Eighty Paise Only
35	35.00	Circillps	Each	197.60	Rupees One Hundred Ninety Seven and Sixty Paise Only

Signature of the Contractor

Executive Engineer

Name Of Work: Maintenance of Existing Borewells in ward no. 05 Kogilu Surrounding area.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NATARAJ T	
				In Figures	In Words
36	56.70	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	Cum	284.74	Rupees Two Hundred Eighty Four and Seventy Four Paise Only
37	210.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.75mm (weight of pipe -0.917 kg)	Mtr	223.88	Rupees Two Hundred Twenty Three and Eighty Eight Paise Only
38	56.70	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	162.82	Rupees One Hundred Sixty Two and Eighty Two Paise Only
39	600.00	Supply of Drinking Water through water tankers of Capacity 5000 Liters Hiring of Water Tanker. Hire Charges of Tractor 40 HP including Operator and Fuel. Procurement of Water. Providing causal labours (unskilled mazdoor heavy).	1	569.09	Rupees Five Hundred Sixty Nine and Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike